

TYPICAL FLOOR
(10TH FLOOR TO 16TH FLOOR)
(18TH FLOOR TO 19TH FLOOR)
(TOWER–B & G)

TOWER–B & G	
TYPICAL FLOOR	TOWER–B / TOWER–G
10TH FLOOR	+37700 / +38940
11TH FLOOR	+41750 / +43240
12TH FLOOR	+45800 / +47540
13TH FLOOR	+49850 / +50540
14TH FLOOR	+53550 / +53440
15TH FLOOR	+54950 / +56940
16TH FLOOR	+56300 / +60340
18TH FLOOR	+65700 / +65740
19TH FLOOR	+68850 / +70940



TYPICAL(10TH TO 16TH & 18TH TO 19TH) FLOOR
TOWER–B & G

AREA CALCULATION OF TYPICAL (10th TO 16th, 18th TO 19th) FLOOR							
GROSS – A							
a	4	X	1.975	X	3.850	=	27.859 SQM
b	4	X	4.460	X	7.375	=	131.570 SQM
c	4	X	1.100	X	0.450	=	1.980 SQM
d	4	X	2.895	X	0.425	=	4.922 SQM
e	4	X	2.895	X	0.750	=	8.685 SQM
f	4	X	4.425	X	0.400	=	7.080 SQM
g	4	X	4.300	X	1.500	=	25.800 SQM
h	4	X	3.700	X	1.075	=	15.910 SQM
i	4	X	6.365	X	1.425	=	10.821 SQM
j	4	X	6.465	X	0.750	=	19.395 SQM
k	2	X	4.550	X	0.400	=	3.640 SQM
l	2	X	4.325	X	1.500	=	12.975 SQM
m	2	X	3.775	X	1.075	=	8.118 SQM
n	2	X	35.180	X	7.275	=	511.869 SQM
o	2	X	1.800	X	1.420	=	12.312 SQM
p	1	X	31.880	X	9.365	=	298.556 SQM
q	1	X	1.200	X	0.450	=	2.160 SQM
					TOTAL	=	1104.049 SQM
GROSS – B							
a	12	X	0.400	X	0.850	=	4.080 SQM
b	12	X	0.275	X	0.550	=	1.815 SQM
d	4	X	1.575	X	0.800	=	5.040 SQM
e	4	X	5.100	X	2.700	=	13.770 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
h	1	X	0.825	X	1.350	=	1.114 SQM
i	1	X	5.100	X	2.700	=	13.770 SQM
k	1	X	0.800	X	1.000	=	0.800 SQM
l	1	X	0.700	X	1.450	=	1.015 SQM
m	1	X	0.700	X	1.450	=	1.015 SQM
n	1	X	0.700	X	1.450	=	1.015 SQM
o	1	X	2.675	X	2.700	=	7.223 SQM
q	4	X	2.550	X	2.550	=	25.500 SQM
q1	1	X	1.250	X	1.750	=	2.188 SQM
q2	1	X	3.300	X	2.250	=	7.425 SQM
r	1	X	2.000	X	2.700	=	5.400 SQM
r1	1	X	1.900	X	0.350	=	0.665 SQM
s	1	X	1.850	X	0.750	=	1.238 SQM
t	1	X	1.650	X	0.550	=	0.908 SQM
u	1	X	1.500	X	0.480	=	0.480 SQM
v	1	X	5.100	X	2.700	=	13.770 SQM
				TOTAL		=	94.274 SQM
TOTAL FAR AREA OF TYPICAL (10th TO 16th,18th TO 19th) FLOOR			=	GROSS – A	-	GROSS – B	
			=	1104.049	-	94.274	
			=	1009.776	SQM		
BUILTUP AREA							
GROSS – C							
a	1	X	5.100	X	2.700	=	13.770 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
v	1	X	5.400	X	1.200	=	6.480 SQM
v	1	X	5.100	X	2.700	=	13.770 SQM
				TOTAL		=	29.790 SQM
TOTAL BUILTUP AREA OF TYPICAL (10th TO 16th,18th TO 19th) FLOOR			=	FAR AREA	+	GROSS – C	
			=	1009.776	+	29.790	
			=	1039.566	SQM		
TOTAL NON FAR AREA OF TYPICAL (10th TO 16th,18th TO 19th) FLOOR	=	BUILTUP AREA	-	FAR AREA			
	=	1039.566	-	1009.776			
	=	29.790	SQM				



PART PLAN (POWDER ROOM)



SECTION : A-A

TYPICAL MECHANICAL VENTILATION CALCULATION FOR POWDER ROOM								
S. NO.	LOCATION	AREA (SQ.ft)	HEIGHT (Ft.)	VOLUME (Cu.ft)	DESIGN CFM	SELECTED EXHAUST FAN CFM	FAN SIZE DIA	EXHAUST DUCT SIZE DIAMETER (mm)
1	TYPICAL MECHANICAL VENTILATION FOR POWDER ROOM							
1.1	POWDER ROOM	28.4	9	238	47.60	1#100cfm cassette in line fan	150	110(OD)

DOOR AND WINDOW SCHEDULE (TYPICAL AND REFUSE FLOOR)							
SR. NO.	NAME	ROUGH OPENING	ROUGH OPENING HEIGHT	SILL LVL	LINTEL LVL	LOCATION	TYPE
1	D1	900	2420	0	2420	KITCHEN	UPVC
2	D2	800	2420	0	2420	TOILETS & UTILITY& POWDER ROOM	UPVC
3	D2a	800	2200	0	2200	STAFF TOILET	UPVC
4	D3	1000	2420	0	2420	BEDROOMS, UTILITY, UNISEX TOILET	UPVC
5	D3a	1000	2200	0	2200	UTILITY BALCONY	UPVC
6	SD1	2495	2600	0	2600	MASTER BEDROOM	UPVC
7	SD2	1700	0	0	0	BEDROOM 2,3, MULTIPURPOSE PLAYROOM	UPVC
8	SD3	3700	2600	0	2600	LIVING ROOM	UPVC
9	SD4	2165	2600	0	2600	BEDROOM 4	UPVC
10	DW1	1500	1550	1050	2600	KITCHEN	UPVC
11	W1	600	1100	1350	2450	TOILET	UPVC
12	W2	700	1550	1050	2600	MASTER BEDROOM	UPVC
13	W3	600	1550	1050	2600	UTILITY TOILET	UPVC
14	W4	1000	1550	1050	2200	SERVICE AREA, STORE ROOM	UPVC
15	W7	600	1450	1350	2800	MASTER BEDROOM TOILET	UPVC
16	FD	1200	2420	0	2420	ENTRANCE DOOR	2HR FIRE RATED
17	FDa	1200	2420	0	2420	FIRE TOWER	2HR FIRE RATED
18	FD1	1200	2130	0	2130	STAIRCASE	2HR FIRE RATED
19	FD4	750	2050	100	2150	SERVICE & LIV.SHAFT	2HR FIRE RATED
20	FD5	1000	2050	100	2150	ELEC. SHAFT	2HR FIRE RATED
21	FC1	900	2050	100	2150	FHC	AS/VENDOR
22	FD8	1000	2420	0	2420	CORRIDOR	2HR FIRE RATED
23	FD9	2000	2420	0	2420	SOCIALIZED AREA	2HR FIRE RATED



17th REFUGE FLOOR

REFUGE AREA CALCULATION – 17TH. REFUGE FLOOR								
GROSS – A								
r1	=	1	X	2.060	X	5.230	=	10.775 SQM
r2	=	1	X	4.510	X	7.245	=	32.675 SQM
r3	=	1	X	4.400	X	0.328	=	1.430 SQM
					TOTAL	=	44.880	SQM
GROSS – B								
x1	=	1	X	1.200	X	0.900	=	1.080 SQM
					TOTAL	=	1.080	SQM
TOTAL REFUGE AREA	=	GROSS – A	-	GROSS – B				
	=	44.880		1.080				
	=	43.800	SQM					
GROSS AREA OF 17TH FLOOR	=	788.471	SQM					
GROSS AREA OF TYPICAL 18TH FLOOR	=	1004.675	SQM					
TOTAL	=	1793.146	SQM					

TOTAL NO. OF OCCUPANTS	=	GROSS AREA	/	OCCUPANT FACTOR		
	=	1793.146	/	12.5	=	143 PERSONS
REFUGE AREA REQUIRED	=	0.3 SQM. PER PERSON	*	0.9 SQM. ADDITIONAL SPAE TO ACCOMMODATE WHEEL CHAIR		
	=	0.3	X	143	=	0.9
	=	42.900		+		0.9
PROPOSED REFUGE AREA	=	43.800	SQM.			



17TH FLOOR
(TOWER–B & G)

TOWER–B & G		
TYPICAL FLOOR	TOWER–B	TOWER–G
17TH FLOOR	+61700	+63640



17th (REFUGE) FLOOR AREA
TOWER–B & G

AREA CALCULATION OF 17TH REFUGE FLOOR							
GROSS – A							
a	3	X	1.100	X	0.450	=	1.485 SQM
b	3	X	2.895	X	0.425	=	3.691 SQM
c	3	X	2.895	X	0.750	=	6.728 SQM
d	3	X	4.425	X	0.400	=	5.310 SQM
e	3	X	4.300	X	1.500	=	19.350 SQM
f	3	X	3.700	X	1.075	=	11.933 SQM
g	3	X	6.365	X	1.425	=	8.115 SQM
h	3	X	6.465	X	0.750	=	14.546 SQM
i	3	X	4.550	X	0.400	=	5.460 SQM
j	3	X	4.325	X	1.500	=	19.463 SQM
k	1	X	3.775	X	1.075	=	4.058 SQM
l	1	X	1.800	X	3.830	=	20.988 SQM
m	1	X	4.460	X	7.375	=	86.678 SQM
n	1	X	35.180	X	7.275	=	255.933 SQM
o	1	X	31.880	X	7.375	=	84.843 SQM
p	1	X	2.233	X	1.810	=	4.045 SQM
q	1	X	0.600	X	0.550	=	0.330 SQM
r	1	X	5.500	X	1.880	=	10.374 SQM
s	1	X	2.115	X	1.180	=	2.490 SQM
t	1	X	23.545	X	1.485	=	34.960 SQM
u	1	X	4.700	X	1.475	=	6.933 SQM
v	1	X	22.995	X	0.465	=	10.692 SQM
w	1	X	4.725	X	9.059	=	42.806 SQM
x	1	X	16.040	X	5.445	=	55.258 SQM
y	1	X	17.890	X	7.275	=	128.665 SQM
z	1	X	1.985	X	1.075	=	2.134 SQM
z1	1	X	2.080	X	1.800	=	3.590 SQM
z1	1	X	2.375	X	0.450	=	0.960 SQM
z2	1	X	1.200	X	0.450	=	0.180 SQM
					TOTAL	=	865.308 SQM
GROSS – B							
a	9	X	0.400	X	0.850	=	3.060 SQM
d	3	X	0.275	X	0.550	=	1.361 SQM
e	3	X	1.575	X	0.800	=	3.780 SQM
f	1	X	4.725	X	1.350	=	4.101 SQM
g	1	X	0.825	X	1.350	=	0.844 SQM
h	4	X	5.100	X	2.700	=	13.770 SQM
i	1	X	0.800	X	1.000	=	0.800 SQM
j	1	X	0.700	X	1.350	=	0.873 SQM
k	1	X	0.700	X	1.450	=	1.015 SQM
l	1	X	0.700	X	1.450	=	1.041 SQM
m	4	X	2.550	X	2.550	=	25.500 SQM
n	1	X	2.080	X	2.270	=	4.721 SQM
o	1	X	5.650	X	1.200	=	6.780 SQM
q	1	X	6.100	X	1.500	=	7.650 SQM
r	1	X	1.250	X	1.600	=	2.000 SQM
s	1	X	1.850	X	0.750	=	1.238 SQM
t	1	X	1.650	X	0.550	=	0.908 SQM
u	1	X	2.000	X	2.700	=	5.400 SQM
u1	1	X	1.900	X	0.350	=	0.665 SQM
					TOTAL	=	89.763 SQM
TOTAL FAR AREA OF 17TH REFUGE FLOOR	=	GROSS – A	-	GROSS – B			
	=	865.308	-	89.763			
	=	795.546	SQM				
BUILTUP AREA							
GROSS – C							
a	1	X	5.100	X	2.700	=	13.770 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
v	1	X	5.400	X	1.200	=	6.480 SQM
v	1	X	5.100	X	2.700	=	13.770 SQM
					TOTAL	=	35.790 SQM
TOTAL BUILTUP AREA OF 17TH REFUGE FLOOR	=	FAR AREA	+	GROSS – C			
	=	795.546	+	359.607			
	=	1055.153	SQM				
TOTAL NON FAR AREA OF 17TH REFUGE FLOOR	=	BUILTUP AREA	-	FAR AREA			
	=	1055.153	-	795.546			
	=	359.607	SQM				

LIFT CAPACITY			
SR. NO.	Shaft Size (mm)	Car Size (mm)	Capacity
1	2550x2450	2000x 1550x2700	20PI 1360Kg
2	1900x3000	1100x2200x2700	16PI 1088Kg
3	2550x2450	1600x 1900x2700	20PI 1360Kg

DIMENSION LEGEND:	
1525	ARCHITECTURE DIM.
1525	AREA SIM.

LEGEND :-

	①	160 OD uPVC SWR CLASS B SOIL / WASTE & VENT PIPE
	③	110 OD uPVC SWR CLASS B ANTISYPHONE PIPE
	④	180 OD uPVC SWR CLASS B VENT/ANTISYPHONE PIPE
	⑤	160 OD uPVC SWR CLASS A MAIN RISER DOWNCOMER PIPE
	⑥	POWER DG WATER SUPPLY DOWNTAKE PIPE CLASS D
	⑦	FLUSHING WATER SUPPLY DOWNTAKE PIPE CLASS D
		110 OD uPVC SWR CLASS A BALCONY DRAIN PIPE
	F.D.	FLOOR DRAIN
DWS		DOMESTIC WATER SUPPLY
FWS		FLUSHING WATER SUPPLY
PRS		PRESSURE REDUCING VALVE STATION

Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

PROJECT

REVISED(1ST REVISION) BUILDING PLANS OF PHASE-1(PRIVANA-SOUTH) FALLING UNDER RESIDENTIAL COLONY UNDER NEW INTEGRATED LICENSING POLICY(NILP) DATED 11.05.2022 ON LAND MEASURING 116.29625 ACRES (LICENCE NO. 219 OF 2023.DATED 25-10-23.) (AN AREA MEASURING 103.05625 ACRES MIGRATION FROM LICENCE NO. 27 OF 2012 DATED 02.04.2012 AND 13.24 ACRES AS FRESH AS FRESH APPLIED AREA) IN SECTOR -76 & 77, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LTD.IN COLLABORATION WITH LAND OWNERS AND IT' S ASSOCIATE COMPANIES

DESIGN ARCHITECTS

Arcop Associates Pvt. Ltd.,
Plot No.–36B,Institutional Area,
Sector–32,Gurgaon,
Haryana–122001.

SUBMISSION ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi–110070.
Tel.: 011–26898616,26898617
www.rsms–arch.com



This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the general public

S.T.P.(HQ) Member Secretary B.P.A.C. | S.T.P.(G) Member B.P.A.C. | CTP(HR) Chairman B.P.A.C.

DTP(HQ) | ATP(HQ) | DIRECTOR (TOWN PLANNING) HQ

Approved/Recommended ok for Public Health Engineering Department Haryana only to commente in its Note/Sheet No. 9552/D dated 31/12/24

PA to ATP(HQ) | ATP(HQ)

TO BE READ WITH THIS OFFICE MEMO NO. 43495 DATED : 13/11/2025

Chief Engineer (HQ) | Superintending Engineer (HQ) | Executive Engineer-I | Executive Engineer-II | Sub Divisional Officer

ARCHITECT'S SEAL & SIGNATURE

Council of Architecture Registration No. / A/1994/50135

OWNER'S SEAL & SIGNATURE

DLF Limited
Authorised Signatory

JAN.–2025 | Scale : 1:100 | NORTH

Drawing Title :–

TYPICAL (10TH TO 16TH,18TH TO 19TH) & 17TH REFUGE FLOOR PLAN OF AREA CALCULATION (TOWER-B & G)

Drawing No. :–

TB-04

1–06052025