

TYPICAL FLOOR
(20TH FLOOR TO 25TH FLOOR)
(27TH FLOOR TO 29TH FLOOR)
(TOWER-B & G)

TOWER-B & G		
TYPICAL FLOOR	TOWER-B	TOWER-G
20TH FLOOR	+71550	+73840
21ST FLOOR	+73350	+75740
22ND FLOOR	+75150	+77640
23RD FLOOR	+76950	+79540
24TH FLOOR	+78750	+81440
25TH FLOOR	+80550	+83340
27TH FLOOR	+84150	+87140
28TH FLOOR	+85950	+88940
29TH FLOOR	+87750	+90740



TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR
TOWER-B & G

TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH)							
GROSS – A							
1	4	X	1.825	X	3.835	=	27.959 SQM
3	4	X	4.460	X	7.375	=	131.570 SQM
4	4	X	1.100	X	0.450	=	1.980 SQM
5	4	X	2.895	X	0.425	=	4.932 SQM
6	4	X	2.995	X	0.750	=	8.981 SQM
7	4	X	4.425	X	0.400	=	7.080 SQM
8	4	X	4.300	X	1.300	=	22.800 SQM
9	4	X	3.700	X	1.075	=	15.910 SQM
10	4	X	4.385	X	0.425	=	10.821 SQM
11	4	X	6.485	X	0.750	=	19.380 SQM
12	4	X	4.555	X	0.400	=	7.288 SQM
13	2	X	4.555	X	1.500	=	12.973 SQM
14	2	X	3.775	X	1.075	=	8.118 SQM
15	4	X	35.180	X	7.375	=	611.869 SQM
16	2	X	1.800	X	3.430	=	12.312 SQM
18	4	X	31.840	X	9.365	=	298.506 SQM
19	4	X	1.200	X	0.450	=	2.160 SQM
					TOTAL	=	1104.049 SQM
GROSS – B							
a	12	X	0.400	X	0.850	=	4.080 SQM
b	12	X	0.375	X	0.550	=	1.815 SQM
c	1	X	3.375	X	0.850	=	2.869 SQM
d	1	X	1.300	X	0.400	=	14.040 SQM
e	1	X	1.475	X	1.200	=	1.770 SQM
h	1	X	0.625	X	1.350	=	0.844 SQM
i	1	X	3.175	X	1.350	=	4.286 SQM
k	1	X	0.950	X	1.000	=	0.900 SQM
m	1	X	0.700	X	1.250	=	0.875 SQM
n	1	X	0.700	X	1.450	=	1.015 SQM
o	1	X	0.950	X	2.673	=	2.541 SQM
q	1	X	2.550	X	3.850	=	49.014 SQM
q1	1	X	1.350	X	1.750	=	2.188 SQM
s2	1	X	3.300	X	2.250	=	7.425 SQM
r	1	X	1.650	X	0.750	=	1.238 SQM
t	1	X	1.800	X	0.350	=	0.665 SQM
u	1	X	1.650	X	0.750	=	1.238 SQM
v	1	X	1.650	X	0.550	=	0.908 SQM
w	1	X	0.400	X	1.200	=	0.480 SQM
x	1	X	5.200	X	2.700	=	14.040 SQM
					TOTAL	=	95.319 SQM

TOTAL FAR AREA OF TYPICAL (20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR	=	GROSS – A	-	GROSS – B	
	=	1104.049	-	95.319	
	=	1008.731	SQM		

BUILTUP AREA							
GROSS – C							
f	1	X	5.200	X	2.700	=	14.040 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
w	1	X	0.400	X	1.200	=	0.480 SQM
x	1	X	5.200	X	2.700	=	14.040 SQM
					TOTAL	=	30.330 SQM

TOTAL BUILTUP AREA OF TYPICAL (20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR	=	FAR AREA	-	GROSS – C	
	=	1008.731	-	30.330	
	=	1039.061	SQM		

TOTAL NON FAR AREA OF TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR	=	BUILTUP AREA	-	FAR AREA	
	=	1039.061	-	1008.731	
	=	30.330	SQM		



PART PLAN (POWDER ROOM)

SECTION : A-A

TYPICAL MECHANICAL VENTILATION CALCULATION FOR POWDER ROOM								
S. NO.	LOCATION	AREA (SQ.M)	HEIGHT (FT.)	VOLUME (CU.M)	DESIGN CFM	SELECTED EXHAUST FAN	FAN SIZE DIA.	EXHAUST DUCT SIZE DIAMETER (MM)
TYPICAL MECHANICAL VENTILATION FOR POWDER ROOM								
1.1	POWDER ROOM	26.4	9	238	47.60	1#100cfm cassette in line fan	150	150(DD)

DOOR AND WINDOW SCHEDULE (TYPICAL AND REFUSE FLOOR)						
SR. NO.	NAME	ROUGH OPENING	ROUGH OPENING HEIGHT	SILL LVL	LINTEL LVL	LOCATION	TYPE
1	D1	900	2420	0	2420	KITCHEN	UPVC
2	D2	800	2420	0	2420	TOILETS & UTILITY& POWDER ROOM	UPVC
3	D2a	800	2200	0	2200	STAFF TOILET	UPVC
4	D3	1000	2420	0	2420	BEDROOMS, UTILITY, UNISEX TOILET	UPVC
5	D3a	1000	2200	0	2200	UTILITY BALCONY	UPVC
6	SD1	2495	2600	0	2600	MASTER BEDROOM	UPVC
7	SD2	1700	0	0	0	BEDROOM 2,3, MULTIPURPOSE PLAYROOM	UPVC
8	SD3	3700	2600	0	2600	LIVING ROOM	UPVC
9	SD4	2165	2600	0	2600	BEDROOM 4	UPVC
10	DW1	1500	1550	1050	2600	KITCHEN	UPVC
11	W1	600	1100	1350	2450	TOILET	UPVC
12	W2	700	1550	1050	2600	MASTER BEDROOM	UPVC
13	W3	600	1550	1050	2600	UTILITY TOILET	UPVC
14	W4	1000	1150	1050	2200	SERVICE AREA, STORE ROOM	UPVC
15	W7	600	1450	1350	2800	MASTER BEDROOM TOILET	UPVC
16	FD	1200	2420	0	2420	ENTRANCE DOOR	2HR FIRE RATED
17	FDa	1200	2420	0	2420	FIRE TOWER	2HR FIRE RATED
18	FD1	1200	2150	0	2150	STAIRCASE	2HR FIRE RATED
19	FD4	750	2050	100	2150	SERVICE & LV SHAFT	2HR FIRE RATED
20	FD5	1000	2050	100	2150	ELEC. SHAFT	2HR FIRE RATED
21	FC1	900	2050	100	2150	AHU/VENDOR	2HR FIRE RATED
22	FD8	1000	2420	0	2420	CORRIDOR	2HR FIRE RATED
23	FD9	2000	2420	0	2420	SOCIALIZED AREA	2HR FIRE RATED



28th REFUGE FLOOR

REFUGE AREA CALCULATION - 28TH REFUGE FLOOR									
GROSS – A									
r1	=	1	X	2.065	X	0.053	=	12.434	SQM
r2	=	1	X	4.400	X	0.325	=	1.430	SQM
r3	=	1	X	7.345	X	4.915	=	33.183	SQM
						TOTAL	=	46.027	SQM
GROSS – B									
r1	=	1	X	1.200	X	0.900	=	1.080	SQM
						TOTAL	=	1.080	SQM
TOTAL REFUGE AREA	=	GROSS – A	-	GROSS – B					
	=	46.027		1.080					
	=	45.947	SQM						
GROSS AREA OF 28TH. FLOOR (REFUGE)	=	788.390	SQM						
GROSS AREA OF TYPICAL(1ST TO 25TH & 27TH TO 30TH) FLOOR	=	1008.404	SQM						
TOTAL	=	1794.794	SQM						
TOTAL NO. OF OCCUPANT	=	1794.794/12.5	=	144	PERSONS				
REFUGE AREA REQUIRED	=	144X0.3	+	0.9(ADDITIONAL SPACE TO ACCOMMODATE WHEEL CHAIR SPACE @0.9 SQM PER 200 POPULATION)					
	=	43.200	+	0.9					
	=	44.100	SQM						
REFUGE AREA PROVIDED	=	43.947	SQM						



26TH FLOOR (REFUGE) PLAN
(TOWER-B & G)

TOWER-B & G		
TYPICAL FLOOR	TOWER-B	TOWER-G
26TH FLOOR	+83350	+85640



26th REFUGE FLOOR
TOWER-B & G

AREA CALCULATION OF 26TH REFUGE FLOOR							
GROSS – A							
1	1	X	1.100	X	0.450	=	0.495 SQM
2	1	X	1.825	X	3.835	=	20.869 SQM
3	3	X	4.460	X	7.375	=	98.678 SQM
4	1	X	1.100	X	0.450	=	0.990 SQM
5	3	X	2.895	X	0.425	=	3.691 SQM
6	3	X	2.995	X	0.750	=	6.733 SQM
7	3	X	4.425	X	0.400	=	5.310 SQM
8	3	X	4.300	X	1.300	=	17.100 SQM
9	3	X	3.700	X	1.075	=	11.933 SQM
10	3	X	6.385	X	0.425	=	8.115 SQM
11	3	X	6.485	X	0.750	=	14.546 SQM
12	3	X	4.555	X	0.400	=	5.466 SQM
13	1	X	4.555	X	1.500	=	6.836 SQM
14	1	X	3.775	X	1.075	=	4.059 SQM
15	3	X	35.180	X	7.375	=	458.902 SQM
16	1	X	1.800	X	3.430	=	6.156 SQM
17	1	X	18.040	X	9.365	=	169.015 SQM
18	1	X	17.490	X	7.375	=	128.956 SQM
20	1	X	1.985	X	1.075	=	2.134 SQM
21	1	X	2.260	X	1.500	=	3.390 SQM
22	1	X	2.375	X	0.400	=	0.950 SQM
23	1	X	6.725	X	1.850	=	49.014 SQM
24	1	X	6.825	X	0.800	=	40.404 SQM
25	1	X	4.700	X	0.450	=	21.150 SQM
26	1	X	2.110	X	0.775	=	1.635 SQM
28	1	X	3.600	X	1.835	=	6.593 SQM
29	1	X	0.800	X	0.550	=	0.308 SQM
30	1	X	3.235	X	1.810	=	4.045 SQM
31	1	X	4.225	X	2.875	=	12.368 SQM
32	4	X	1.200	X	0.450	=	2.160 SQM
					TOTAL	=	884.427 SQM
GROSS – B							
a	9	X	0.400	X	0.850	=	3.060 SQM
b	9	X	0.375	X	0.550	=	1.361 SQM
c	1	X	3.375	X	0.850	=	2.869 SQM
f	1	X	5.200	X	2.700	=	14.040 SQM
h	1	X	0.625	X	1.350	=	0.844 SQM
i	1	X	3.175	X	1.350	=	4.286 SQM
k	1	X	0.950	X	1.000	=	0.900 SQM
m	1	X	0.700	X	1.250	=	0.875 SQM
n	1	X	0.700	X	1.450	=	1.015 SQM
o	1	X	0.950	X	2.673	=	2.541 SQM
q	1	X	2.550	X	3.850	=	24.590 SQM
q1	1	X	3.300	X	2.250	=	7.425 SQM
r	1	X	2.100	X	3.000	=	6.300 SQM
s	1	X	1.650	X	0.750	=	1.238 SQM
t	1	X	1.800	X	0.350	=	0.908 SQM
u	1	X	1.800	X	1.200	=	2.160 SQM
w	1	X	1.200	X	0.400	=	0.480 SQM
v	1	X	5.200	X	2.700	=	14.040 SQM
					TOTAL	=	90.363 SQM

TOTAL FAR AREA OF 26TH REFUGE FLOOR	=	GROSS – A	-	GROSS – B	
	=	884.427	-	90.363	
	=	794.164	SQM		

BUILTUP AREA OF 26TH REFUGE FLOOR							
GROSS – C							
f	1	X	5.200	X	2.700	=	14.040 SQM
u	1	X	1.800	X	1.200	=	2.160 SQM
w1	1	X	1.200	X	0.450	=	0.540 SQM
v	1	X	5.200	X	2.700	=	14.040 SQM
a2	3	X	0.400	X	0.850	=	1.020 SQM
b2	3	X	0.375	X	0.550	=	0.619 SQM
m3	1	X	2.880	X	0.480	=	1.037 SQM
n5	1	X	2.780	X	0.445	=	9.577 SQM
n6	1	X	10.765	X	2.805	=	26.966 SQM
s7	1	X	4.460	X	1.855	=	11.618 SQM
s8	1	X	1.825	X	1.830	=	6.990 SQM
s9	1	X	0.900	X	3.220	=	4.659 SQM
s10	1	X	21.000	X	5.945	=	124.845 SQM
s11	1	X	4.300	X	1.855	=	8.000 SQM
s12	1	X	4.425	X	0.400	=	1.770 SQM
s13	1	X	8.575	X	4.915	=	42.151 SQM
					TOTAL	=	280.815 SQM

TOTAL BUILTUP AREA OF 26TH REFUGE FLOOR	=	FAR AREA	-	GROSS – C	
	=	794.164	-	280.815	
	=	1068.979	SQM		

TOTAL NON FAR AREA OF 26TH REFUGE FLOOR	=	BUILTUP AREA	-	FAR AREA	
	=	1068.979	-	794.164	
	=	280.815	SQM		

Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

PROJECT

REVISED(1ST REVISION) BUILDING PLANS OF PHASE-1(PRIVANA-SOUTH) FALLING UNDER RESIDENTIAL COLONY
UNDER NEW INTEGRATED LICENSING POLICY(NILP) DATED 11.05.2022 ON LAND MEASURING 116.29625 ACRES (LICENCE NO. 219 OF 2023,DATED 25-10-23) (AN AREA MEASURING 103.05625 ACRES MIGRATION FROM LICENCE NO. 27 OF 2012 DATED 02.04.2012 AND 13.24 ACRES AS FRESH AS FRESH APPLIED AREA) IN SECTOR -76 & 77, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LTD.IN COLLABORATION WITH LAND OWNERS AND IT' S ASSOCIATE COMPANIES

DESIGN ARCHITECTS

Arcop Associates Pvt. Ltd.,
Plot No.-36B,Institutional Area,
Sector-32,Gurgaon,
Haryana-122001.

SUBMISSION ARCHITECTS

RSMS ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi-110070.
Tel.: 011-26898616,26898617
www.rsms-arch.com



This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the general public

S.T.P.(HQ) Member Secretary B.P.A.C. | S.T.P.(G) Member B.P.A.C. | CTP.(HR.) Chairman B.P.A.C.

DTP(HQ) | ATP(HQ) | DIRECTOR KUMAR PA(HQ)

JOD. | PA. | ATP(HQ)

TO BE READ WITH LETTER OF (HQ) MEMO NO.: 4777 DATED : 17/11/2025

Checked and found ok for Public Health Engineering Service only subject to comments in Forwarding letter No. 35320 dt. 21/11/2025

ARCHITECT'S SEAL & SIGNATURE | OWNER'S SEAL & SIGNATURE

Chief Engineer (HQ) HSVP Panchkula

DLF Limited
Authorised Signatory

JAN.-2025 | Scale : 1:100 | NORTH

Drawing Title:-
TYPICAL 20TH TO 25TH,27TH TO 29TH FLOOR PLAN
26TH REFUGE FLOOR
OF AREA CALCULATION
(TOWER-B & G)

Drawing No:-
TB-05
1-06052025

LEGEND :-

SVP	1	160 DIA uPVC SWR CLASS B SOIL / WASTE & VENT PIPE
RWP	2	110 DIA uPVC SWR CLASS B ANTISYPHONIC PIPE
VP	3	110 DIA uPVC SWR CLASS B KITCHEN WASTE PIPE
	4	160 DIA uPVC SWR CLASS A RAIN WATER DOWNCAST PIPE
CWP	5	DOMESTIC WATER SUPPLY DOWNTAKE PIPE (IS CLASS C)
FWP	6	FLUSHING WATER SUPPLY DOWNTAKE PIPE (IS CLASS C)
	7	110 DIA uPVC SWR CLASS A BALCONY DRAIN PIPE
FD	8	FLOOR DRAIN
DWS		DOMESTIC WATER SUPPLY
FWS		FLUSHING WATER SUPPLY
PRV		PRESSURE REDUCING VALVE STATION

DIMENSION LEGEND
1525 ARCHITECTURE DIM.
1525 AREA DIM.

LIFT CAPACITY

S/R. NO.	Shaft Size (mm)	Car Size (mm)	Capacity
1	2550x2450	2000x1550x2700	20PI 1360Kg
2	1900x3000	1100x2300x2700	16PI 1088Kg
3	2550x2450	1600x1900x2700	20PI 1360Kg