

TYPICAL FLOOR
(20TH FLOOR TO 25TH FLOOR)
(27TH FLOOR TO 29TH FLOOR)
(TOWER-F)



TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR
TOWER-F

TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) TOWER-F							
GROSS – A							
2	4	X	1.825	X	3.830	=	27.959 SQM
3	4	X	4.460	X	7.375	=	131.670 SQM
4	4	X	1.100	X	0.450	=	1.980 SQM
5	4	X	2.895	X	1.425	=	4.502 SQM
6	4	X	2.895	X	0.750	=	8.985 SQM
7	4	X	4.460	X	1.400	=	24.976 SQM
8	4	X	4.350	X	1.500	=	26.100 SQM
9	4	X	3.700	X	1.075	=	15.910 SQM
10	4	X	6.360	X	0.425	=	10.831 SQM
11	4	X	6.460	X	0.750	=	19.380 SQM
12	2	X	4.350	X	0.400	=	3.540 SQM
13	2	X	4.325	X	1.500	=	12.975 SQM
14	2	X	3.775	X	1.075	=	8.116 SQM
15	2	X	38.180	X	7.275	=	511.869 SQM
16	2	X	1.800	X	1.425	=	12.312 SQM
17	2	X	31.880	X	9.360	=	298.556 SQM
18	2	X	1.450	X	0.450	=	2.160 SQM
19	2	X	1.329	X	1.075	=	8.745 SQM
				TOTAL		=	1112.794 SQM
GROSS – B							
a	12	X	0.400	X	0.850	=	4.080 SQM
b	12	X	0.275	X	0.550	=	1.815 SQM
d	4	X	1.675	X	0.800	=	5.540 SQM
e	1	X	5.200	X	2.700	=	14.040 SQM
g	1	X	1.475	X	1.200	=	1.770 SQM
h	1	X	0.825	X	1.350	=	0.844 SQM
i	1	X	3.175	X	1.350	=	4.286 SQM
j	1	X	5.200	X	1.000	=	5.200 SQM
m	1	X	0.700	X	1.250	=	0.875 SQM
n	1	X	0.750	X	1.250	=	0.938 SQM
p	1	X	0.950	X	2.675	=	2.541 SQM
q	4	X	2.550	X	2.500	=	25.500 SQM
s1	1	X	3.300	X	2.250	=	7.425 SQM
r	1	X	2.100	X	2.700	=	5.670 SQM
r1	1	X	1.900	X	0.350	=	0.665 SQM
s	1	X	1.650	X	0.750	=	1.238 SQM
s	1	X	1.650	X	0.550	=	0.908 SQM
t	1	X	1.400	X	1.200	=	1.680 SQM
u	1	X	0.400	X	1.200	=	0.480 SQM
v	1	X	5.200	X	2.700	=	14.040 SQM
w	2	X	1.175	X	2.300	=	5.405 SQM
				TOTAL		=	101.899 SQM

TOTAL FAR AREA OF TYPICAL (20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR (TOWER-F)	=	GROSS – A	GROSS – B
	=	1112.794	101.899
	=	1010.896 SQM	

BUILTUP AREA							
GROSS – C							
a	1	X	5.200	X	2.700	=	14.040 SQM
g	1	X	5.200	X	2.700	=	14.040 SQM
u	1	X	0.400	X	1.200	=	0.480 SQM
v	1	X	5.200	X	2.700	=	14.040 SQM
				TOTAL		=	36.330 SQM

TOTAL BUILTUP AREA OF TYPICAL (20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR (TOWER-F)	=	FAR AREA	-	GROSS – C	
	=	1010.896	-	36.330	
	=	1041.226	SQM		
TOTAL NON FAR AREA OF TYPICAL(20TH TO 25TH ,27TH TO 34TH & 36TH TO 40TH) FLOOR (TOWER-F)	=	BUILTUP AREA	-	FAR AREA	
	=	1041.226	-	1010.896	
	=	36.330	SQM		

DOOR AND WINDOW SCHEDULE (TYPICAL AND REFUSE FLOOR)							
SR. NO.	NAME	ROUGH OPENING	ROUGH OPENING HEIGHT	SILL LVL	LINTEL LVL	LOCATION	TYPE
1	D1	900	2420	0	2420	KITCHEN	UPVC
2	D2	800	2420	0	2420	TOILETS & UTILITY& POWDER ROOM	UPVC
3	D2a	800	2200	0	2200	STAFF TOILET	UPVC
4	D3	1000	2420	0	2420	BEDROOMS, UTILITY, UNISEX TOILET	UPVC
5	D3a	1000	2200	0	2200	UTILITY BALCONY	UPVC
6	SD1	2495	2600	0	2600	MASTER BEDROOM	UPVC
7	SD2	1700	0	0	0	BEDROOM 2,3, MULTIPURPOSE PLAYROOM	UPVC
8	SD3	3700	2600	0	2600	LIVING ROOM	UPVC
9	SD4	2165	2600	0	2600	BEDROOM 4	UPVC
10	DW1	1500	1550	1050	2600	KITCHEN	UPVC
11	W1	600	1100	1350	2450	TOILET	UPVC
12	W2	700	1550	1050	2600	MASTER BEDROOM	UPVC
13	W3	600	1550	1050	2600	UTILITY TOILET	UPVC
14	W4	1000	1150	1050	2200	SERVICE AREA, STORE ROOM	UPVC
15	W7	600	1450	1350	2800	MASTER BEDROOM TOILET	UPVC
16	FD	1200	2420	0	2420	ENTRANCE DOOR	2HR FIRE RATED
17	FDa	1200	2420	0	2420	FIRE TOWER	2HR FIRE RATED
18	FD1	1200	2150	0	2150	STAIRCASE	2HR FIRE RATED
19	FD4	750	2050	100	2150	SERVICE & LV SHAFT	2HR FIRE RATED
20	FD5	1000	2050	100	2150	ELEC. SHAFT	2HR FIRE RATED
21	FC1	900	2050	100	2150	FHC	AS/VENDOR
22	FD8	1000	2420	0	2420	CORRIDOR	2HR FIRE RATED
23	FD9	2000	2420	0	2420	SOCIALIZED AREA	2HR FIRE RATED



26th REFUGE FLOOR

REFUGE AREA CALCULATION - 26TH REFUGE FLOOR								
GROSS – A								
r2	=	1	X	2.065	X	5.053	=	10.434 SQM
r3	=	1	X	4.425	X	0.325	=	1.430 SQM
			X	7.345	X	4.515	=	33.163 SQM
				TOTAL			=	45.027 SQM
GROSS – B								
s1	=	1	X	1.200	X	0.900	=	1.080 SQM
						TOTAL	=	1.080 SQM
TOTAL REFUGE AREA	=	GROSS – A		GROSS – B				
	=	45.027		1.080				
	=	43.947	SQM					
GROSS AREA OF 26TH. FLOOR (REFUGE)	=	789.390	SQM					
GROSS AREA OF TYPICAL(1ST TO 25TH & 27TH TO 30TH) FLOOR	=	1005.404	SQM					
TOTAL	=	1794.794	SQM					
TOTAL NO. OF OCCUPANT	=	1794.794/12.5	=	144	PERSONS			
REFUGE AREA REQUIRED	=	144X0.3	=	0.9SQ.ADDITIONAL SPACE TO ACCOMMODATE WHEEL CHAIR SPACE @0.9 SQM PER 200 POPULATION)				
	=	43.200	=	0.9				
	=	44.100	SQM					
REFUGE AREA PROVIDED	=	43.947	SQM					

DIMENSION LEGEND:	
1525	ARCHITECTURE DIM.
1525	AREA DIM.

LIFT CAPACITY				
SR. NO.	Shaft Size (mm)	Car Size (mm)	Capacity	
1	2550x2450	2000x1650x2700	20PI 1360Kg	
2	1900x3000	1100x2300x2700	16PI 1088Kg	
3	2550x2450	1600x1900x2700	20PI 1360Kg	



TYPICAL 20TH TO 29TH FLOOR PLAN
LVL. +94500
(TOWER-F)

PART PLAN (POWDER ROOM)

FLOORS	TOWER-F
20TH FLOOR	+74100
21TH FLOOR	+77500
22TH FLOOR	+80900
23TH FLOOR	+84300
24TH FLOOR	+87700
25TH FLOOR	+91100
27TH FLOOR	+97900
28TH FLOOR	+101300
29TH FLOOR	+104700

SECTION : A-A

TYPICAL MECHANICAL VENTILATION DETAILS FOR POWDER ROOM							
S. NO.	LOCATION	AREA	NO. OF PEOPLE	SUPPLY AIR VOLUME	EXHAUST FAN	FAN SIZE	EXHAUST DUCT SIZE
		(SQ.M)	(P.)	(CU.M)	CFM	DIA	DIAMETER (mm)
1.1	TYPICAL MECHANICAL VENTILATION FOR POWDER ROOM						
	POWDER ROOM	26.4	9	238	47.60	1#100cfm cassette in line fan	150

LEGEND		
	1	160 OD uPVC SWR CLASS B SOIL / WASTE & VENT PIPE
	2	110 OD uPVC SWR CLASS B ANTIEPHPHONE PIPE
	4	160 OD uPVC SWR CLASS B KITCHEN WASTE PIPE
	5	160 OD uPVC SWR CLASS A RAIN WATER DOWNTAKE PIPE
		DOMESTIC WATER SUPPLY DOWNTAKE PIPE (OD CLASS C)
	7	FLUSHING WATER SUPPLY DOWNTAKE PIPE (OD CLASS C)
		110 OD uPVC SWR CLASS A BALCONY DRAIN PIPE
	FD	FLOOR DRAIN
DWS		DOMESTIC WATER SUPPLY
FWS		FLUSHING WATER SUPPLY
PRS		PRESSURE REDUCING VALVE STATION

26TH FLOOR (REFUGE) PLAN
LVL. +94500
(TOWER-F)



26th REFUGE FLOOR
TOWER-F

AREA CALCULATION OF 26TH REFUGE FLOOR (TOWER-F)							
GROSS – A							
2	3	X	1.100	X	0.450	=	0.495 SQM
3	3	X	1.825	X	3.830	=	20.969 SQM
4	3	X	4.460	X	7.375	=	98.678 SQM
5	3	X	1.100	X	0.450	=	0.990 SQM
6	3	X	2.895	X	1.425	=	3.981 SQM
7	3	X	2.895	X	0.750	=	6.629 SQM
8	3	X	4.425	X	0.400	=	5.310 SQM
9	3	X	4.350	X	1.500	=	19.350 SQM
10	3	X	3.700	X	1.075	=	11.933 SQM
11	3	X	6.360	X	0.425	=	8.115 SQM
12	3	X	6.460	X	0.750	=	14.546 SQM
13	1	X	4.350	X	0.400	=	1.800 SQM
14	1	X	4.325	X	1.500	=	6.488 SQM
15	1	X	3.775	X	1.075	=	4.056 SQM
16	1	X	38.180	X	7.275	=	255.935 SQM
17	1	X	1.800	X	1.425	=	6.156 SQM
18	1	X	16.040	X	9.360	=	150.135 SQM
19	1	X	17.690	X	7.275	=	128.695 SQM
20	1	X	1.968	X	1.075	=	2.114 SQM
21	1	X	2.250	X	1.500	=	3.390 SQM
22	1	X	6.275	X	1.450	=	9.100 SQM
23	1	X	8.125	X	5.950	=	48.344 SQM
24	1	X	6.460	X	6.300	=	40.698 SQM
25	1	X	4.750	X	3.450	=	16.388 SQM
26	1	X	2.150	X	0.555	=	1.193 SQM
27	1	X	3.750	X	1.855	=	6.953 SQM
29	1	X	0.600	X	0.500	=	0.300 SQM
30	1	X	2.235	X	1.810	=	4.045 SQM
31	1	X	4.225	X	2.975	=	12.569 SQM
32	1	X	1.200	X	0.450	=	2.160 SQM
33	2	X	1.329	X	1.300	=	8.745 SQM
				TOTAL		=	893.172 SQM
GROSS – B							
a	9	X	0.400	X	0.850	=	3.060 SQM
b	9	X	0.275	X	0.550	=	1.361 SQM
d	3	X	1.675	X	0.800	=	3.780 SQM
e	1	X	5.200	X	2.700	=	14.040 SQM
h	1	X	0.825	X	1.350	=	0.844 SQM
i	1	X	3.175	X	1.350	=	4.286 SQM
j	1	X	5.200	X	1.000	=	5.200 SQM
m	1	X	0.700	X	1.250	=	0.875 SQM
n	1	X	0.750	X	1.250	=	0.938 SQM
p	1	X	0.950	X	2.675	=	2.541 SQM
q	4	X	2.550	X	2.500	=	25.500 SQM
s1	1	X	3.300	X	2.250	=	7.425 SQM
r	1	X	2.100	X	2.700	=	5.670 SQM
s	1	X	1.650	X	0.550	=	0.908 SQM
t	1	X	1.400	X	1.200	=	1.680 SQM
u	1	X	0.400	X	1.200	=	0.480 SQM
v	1	X	5.200	X	2.700	=	14.040 SQM
w	2	X	1.175	X	2.300	=	5.405 SQM
				TOTAL		=	87.398 SQM

TOTAL FAR AREA OF 26TH REFUGE FLOOR (TOWER-F)	=	GROSS – A	-	GROSS – B
	=	893.172	-	87.398
	=	795.784	SQM	

BUILTUP AREA OF 26TH REFUGE FLOOR (TOWER-F)							
GROSS – C							
f	1	X	5.200	X	2.700	=	14.040 SQM
i	1	X	1.800	X	1.200	=	2.160 SQM
u1	1	X	1.250	X	0.400	=	0.500 SQM
g	1	X	5.200	X	2.700	=	14.040 SQM
k3	1	X	3.780	X	1.205	=	4.557 SQM
m3	1	X	5.200	X	3.855	=	19.795 SQM
n4	1	X	2.650	X	0.450	=	1.193 SQM
n5	1	X	2.780	X	3.445	=	9.577 SQM
n6	1	X	10.760	X	2.505	=	26.956 SQM
s7	1	X	4.460	X	2.655	=	11.816 SQM
s8	1	X	1.825	X	3.830	=	6.990 SQM
s9	1	X	0.950	X	5.120	=	4.959 SQM
s10	1	X	21.050	X	5.945	=	124.845 SQM
s11	1	X	4.300	X	1.400	=	6.020 SQM
s12	1	X	4.425	X	0.400	=	1.770 SQM
s13	1	X	6.575	X	1.800	=	11.835 SQM
				TOTAL		=	293.015 SQM

TOTAL BUILTUP AREA OF 26TH REFUGE FLOOR (TOWER-F)	=	FAR AREA	+	GROSS – C	
	=	795.784	+	260.915	
	=	1056.699	SQM		
TOTAL NON FAR AREA OF 26TH REFUGE FLOOR (TOWER-F)	=	BUILTUP AREA	-	FAR AREA	
	=	1056.699	-	795.784	
	=	260.915	SQM		



TOWER–F
KEY PLAN

Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

PROJECT

REVISED(1ST REVISION) BUILDING PLANS OF PHASE-1(PRIVANA-SOUTH) FALLING UNDER RESIDENTIAL COLONY UNDER NEW INTEGRATED LICENSING POLICY(NILP) DATED 11.05.2022 ON LAND MEASURING 116.29625 ACRES (LICENCE NO. 219 OF 2023,DATED 25-10-23.) (AN AREA MEASURING 103.05625 ACRES MIGRATION FROM LICENCE NO. 27 OF 2012 DATED 02.04.2012 AND 13.24 ACRES AS FRESH AS FRESH APPLIED AREA) IN SECTOR -76 & 77, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LTD.IN COLLABORATION WITH LAND OWNERS AND IT' S ASSOCIATE COMPANIES

DESIGN ARCHITECTS

Arcop Associates Pvt. Ltd.,
Plot No.–368,Institutional Area,
Sector–32,Gurgaon,
Haryana–122001.

SUBMISSION ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi–110070.
Tel.: 011–26898616,26898617
www.rsms–arch.com

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the general public

S.T.P.(HQ) Member Secretary B.P.A.C. — S.T.P.(O) Member B.P.A.C. — S.T.P.(HR.) Chairman B.P.A.C.

DTP(HQ) — DTP(HQ) — JTP(HQ)

VIDE BUILDING PLANS OFFICE ORDER DATED : 17/1/2025 — DIVISION KUMAR PATHAK

ARCHITECT'S SEAL & SIGNATURE — ARCHITECT B.P.A.C. — OWNER'S SEAL & SIGNATURE

DLF Limited

JAN.–2025 — NORTH

Drawing Title:–

TYPICAL 20TH TO 29TH FLOOR PLAN
26TH REFUSE FLOOR
OF AREA CALCULATION
(TOWER-F)

Checked and Approved for Public Health & Engineering (HQ) (Harish Sharma) Superintending Engineer (HQ) subject to commencing certificate. In forwarding letter No.3532/20 Dated 21/1/2025

DRAWING NO. TF-04

1–06052025