GREEN AREA									
GROSS - A									
gr1	=	0.5	X	(54.745+54.155)	X	1.500	=	81.675	SQM
gr2	=	0.5	X	(37.810+37.450)	X	1.500	=	56.445	SQM
gr3	=	0.5	X	(58.860+59.485)	X	1.500	=	88.759	SQM
gr4	=	0.5	X	(194.515+194.935)	X	1.500	=	292.352	SQM
gr5	=	1	X	18.130	X	1.500	=	27.195	SQM
gr6	=	0.5	X	(62.735+64.045)	X	1.500	=	95.085	SQM
gr7	=	0.5	X	(27.365+28.060)	X	1.500	=	41.569	SQM
gr8	=	0.5	X	(18.955+19.625)	X	1.510	=	29.128	SQM
gr9	=	1	X	20.260	X	1.500	=	30.390	SQM
gr10	=	0.5	X	(146.350+146.385)	X	1.500	=	219.551	SQM
gr11	=	0.5	X	(337.125+338.205)	X	1.500	=	506.498	SQM
gr12	=	0.5	X	(23.590+25.395)	X	1.500	=	36.739	SQM
gr13	=	0.5	X	(11.510+10.605)	X	1.500	=	16.586	SQM
gr14	=	0.5	X	(37.820+38.060)	X	1.530	=	58.048	SQM
						TOTAL	=	1580.019	SQM

GREEN AREA												
NO.	A		B		C				s	AREA OF = S(S-A)(S-B)(S-C)	Area	
GROSS - C												
gr15	25.000	+	42.685	+	33.495	/	2	=	50.59	174946.776	418.266	SQM
gr16	32.785	+	26.005	+	42.685	/	2	=	50.738	181406.461	425.918	SQM
gr17	32.785	+	33.740	+	8.210	/	2	=	37.368	18111.492	134.579	SQM
gr18	33.740	+	37.390	+	20.430	/	2	=	45.78	117230.927	342.390	SQM
gr19	37.390	+	47.355	+	55.440	/	2	=	70.093	763672.139	873.883	SQM
gr21	47.355	+	34.895	+	24.140	/	2	=	53.195	165179.303	406.423	SQM
gr22	34.895	+	38.625	+	20.245	/	2	=	46.883	123617.919	351.593	SQM
gr23	55.440	+	38.625	+	48.310	/	2	=	71.188	835106.114	913.841	SQM
gr25	48.310	+	47.995	+	6.280	/	2	=	51.293	22706.608	150.687	SQM
gr27	35.455	+	47.995	+	26.565	/	2	=	55.008	214518.545	463.161	SQM
gr28	35.455	+	30.710	+	6.160	/	2	=	36.16	4185.410	64.695	SQM
									TOTAL	=	4545.438	SQM

ARC AREA	GREEN AREA																							
GROSS - B																								
gr20	3.14	X	170.155	X	170.155	X	18.76	/	360	-	0.5	X	170.155	-	2.275	X	55.440	=	83.868	SQM
gr24	3.14	X	170.155	X	170.155	X	18.76	/	360	-	0.5	X	170.155	-	2.275	X	55.440	=	83.868	SQM
gr26	3.14	X	4.500	X	4.500	X	88.46	/	360	-	0.5	X	4.500	-	1.275	X	6.280	=	5.498	SQM
gr29	3.14	X	4.500	X	4.500	X	86.41	/	360	-	0.5	X	4.500	-	1.220	X	6.160	=	5.160	SQM
																	TOTAL	=	178.394	SQM

ARC AREA	DEDUCTION																			
GROSS - D																				
d1	3.14	X	60.000	X	60.000	X	19.43	/	360	-	0.5	X	60.000	-	0.860	X	20.245	=	11.457	SQM
d2	3.14	X	60.000	X	60.000	X	19.60	/	360	-	0.5	X	60.000	-	0.875	X	20.430	=	11.478	SQM
																	TOTAL	=	22.935	SQM

TOTAL GREEN AREA	=	GROSS - A	+	GROSS - B	+	GROSS - C	-	GROSS - D
	=	1580.019	+	178.394	+	4545.438	-	22.935
	=	6280.916				SQM		

Note :-

1. BUILDING WILL BE DESIGNED (STRUCTURES) AS PER RELEVANT IS CODES FOR EARTH QUAKE RESISTANCE.

PROJECT

REVISED(1ST REVISION) BUILDING PLANS OF PHASE-1(PRIVANA-SOUTH) FALLING UNDER RESIDENTIAL COLONY UNDER NEW INTEGRATED LICENSING POLICY(NILP) DATED 11.05.2022 ON LAND MEASURING 116.29625 ACRES (LICENCE NO. 219 OF 2023.DATED 25-10-23.) (AN AREA MEASURING 103.05625 ACRES MIGRATION FROM LICENCE NO. 27 OF 2012 DATED 02.04.2012 AND 13.24 ACRES AS FRESH AS FRESH APPLIED AREA) IN SECTOR -76 & 77, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF LTD.IN COLLABORATION WITH LAND OWNERS AND IT' S ASSOCIATE COMPANIES

DESIGN ARCHITECTS

Arcop Associates Pvt. Ltd.,
Plot No.-36B,Institutional Area,
Sector-32,Gurgaon,
Haryana-122001.

SUBMISSION ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi-110070.
Tel.: 011-26898616,26898617
www.rsms-arch.com

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting Objections from the consent public

STP(HQ) Member Secretary BPAC | STP(G) Member BPAC | CTP(NR) Chairman BPAC

DTP(HQ) | ATP(HQ) | P.A. | DINESH KUMAR PA(HQ)

TO BE READ WITH THIS OFFICE MEMO NO. 4379 DATED: 15/11/2025

ARCHITECT'S SEAL & SIGNATURE	OWNER'S SEAL & SIGNATURE
CHANCHAL JAIN REGISTERED ARCHITECT CA/2005/38771	Authorised Signatory

JAN.-2025 | Scale : NTS | NORTH

Drawing Title:- GREEN AREA CALCULATION

Drawing No:- ST-03

1-06052025