EXTENSION OF ROOF LINE SHOWN IN ELEVATION
WATERPROOFING LAID TO SLOPE
LIFT MACHINE ROOM
TERRACE
OFFICE
PASS
PARKING
DRIVEWAY
PLAZA DOUBLE HIGHT
GLAZING
LOUVRED/GRILL/MESH
TOP LVL +63550 LVL.
LMR LVL +60150 LVL. +60100VL.
TERRACE FLOOR F.F.L. +58025 LVL. T.O.S.+57725 LVL.
12TH FLOOR F.F.L. +53400 LVL. T.O.S.+53325 LVL.
11TH FLOOR F.F.L. +49000 LVL. T.O.S.+48925 LVL.
10TH FLOOR F.F.L. +44600 LVL. T.O.S.+44525 LVL.
ENT. HALL F.F.L. +1000 LVL. T.O.S.+ 325 LVL.
GR LVL ±00
BASEMENT LVL-1 F.F.L. -4650 LVL. T.O.S. -4650LVL.
BASEMENT LVL-2 F.F.L. -8400 LVL. T.O.S. -8400LVL.
BASEMENT LVL-3 F.F.L. -12150 LVL. T.O.S. -12150LVL.
BASEMENT LVL-4 F.F.L. -15900 LVL. T.O.S.-15900 LVL.
BLOCK A-11TH FLOOR
BLOCK B-12TH FLOOR
BLOCK C-12TH FLOOR
334800

SECTION-A-A



KEY PLAN

DRG NO. SS-S-101

KEY PLAN



NOTES

This development have been conceived, designed and drafted on basis of the following parameters:

1. All toilets will be mechanically ventilated. Conditioned air from the office floor will be sucked in to the toilets and vented out through a vent shaft
2. All spaces (parking basement,
3. service basement ect.) will be artificially lit. Any service basement ect.) will be artificially lit. Any natural light which is available in the office spaces is only incidental and not essential to the functioning of the buildings.
4. 100% standby generating capacity will be provided for the entire electrical requirement of the total scheme. This therefore includes standby generation for all common services, fire services, lifts etc. and also the entire electrical load for ventilation & air-conditioning lights and all office equipment.
5. This building will be sprinkled as per NBC norms.
6. Partitions/modifications for interior space /layout shall be as per client request/requirements of usable area of floor plate

DOOR SCHEDULE

TYPE	OPENING SIZE	CILL	LINTEL	REMARKS
D1	750X2100	±0 0	+2100	INETRNAL TOILET DOOR (SINGLE LEAF)
D2	900X2100	±0 0	+2100	PANTRY/TOILET DOOR (SINGLE LEAF)
D3	1050X2100	±0 0	+2100	HANDICAPPED TOILET (SINGLE LEAF)
D4	1200X2100	±0 0	+2100	LIFT LOBBY DOOR(SINGLE LEAF)
D5	1200X2100	±0 0	+2100	AHU ROOM (2HRS FIRE RATED)(SINGLE LEAF)
D6	2000X2400	±0 0	+2400	OFFICE MAIN DOOR (DOUBLE LEAF) [2HRS FIRE RATED]
D7	2000X2100	±0 0	+2100	SHUTTLE LIFT LOBBY (DOUBLE LEAF) [2HRS FIRE RATED]
D8	2400X3000	±0 0	+3000	GLASS DOOR ENTRANCE HALL/ATRIUM (DOUBLE LEAF)
FD	1700X2100	±0 0	+2100	STAIRCASE DOOR (2HRS FIRE RATED) (DOUBLE LEAF)
FD1	1250X2100	±0 0	+2100	STAIRCASE DOOR/FIRE EXIT DOOR FOR OFFICES(2HRS FIRE RATED)(DOUBLE LEAF)
FD2	900X1800	+300	+2100	FHC DOOR
FD3	1000X2100	±0 0	+2100	ODU/ELECTRICAL ROOM (SINGLE LEAF) (2HRS FIRE RATED)
SD1	600X1250	1100	+2350	ELV ROOM
SD2	745X1250	1100	+2350	PLUMBING
SD3	750X1250	1100	+2350	PLUMBING.CNDSR. PRECOOLED .CHW,PRO

Architect Hafeez Contractor
29 Bank Street, Bombay 400 023. Tel:2661920

PROJECT:-
REVISED BUILDING PLAN OF CYBERPARK COLONY AREA MEASURING 11.816 ACRES(LICENCE NO.180 OF 2007 DATED 02.05.2007 IN SECTOR 20, GURGAON MANESAR URBAN COMPLEX

OWNER:
DLF CYBER CITY DEVELOPERS LTD.

CONSULTANT:-
ARCHITECT(H.Q.)
S.T.P. Member Secretary B.P.C
S.T.P. (G) Member B.P.C
C.T.P. (Hr.) Chairman B.P.C
F.O.
DFS
Member B.P.C.
JD
PA
ATP

DRG.TITLE:-
(BALWANT SINGH) S.D.
SECTION -A-A
(RAM AVTAR BASSI) A.D.

REVISION	JOB NO:-	DRG NO:- SS-S-101	
	SCALE:- 1:250	DATE:- 21/08/2017	
FILE:-	DEALT BY:-	CHECKED BY:	APPROVED BY:-

SIGNATURE & SEAL OF ARCHITECT:-
SIDDHARTH AGARWAL
CA/2014/63620

SIGNATURE & SEAL OF OWNER:-
DLF CYBER CITY DEVELOPERS LIMITED