


BASEMENT PLAN LVL-2 F.F.L. -8400 LVL. T.O.S.-8400 LVL. (+229.60 AMSL)

(NOS OF PARKING - 858)

DRG NO. BP-102

KEY PLAN

BLOCK-A BLOCK-B BLOCK-C

NOTES

This development have been conceived, designed and drafted on basis of the following parameters:

1. All toilets will be mechanically ventilated. Conditioned air from the office floor will be sucked in to the toilets and vented out through a vent shaft
2. All spaces (parking basement, service basement ect) will be artificially lit. Any service basement ect) will be artificially lit. Any natural light which is available in the office spaces is only incidental and not essential to the functioning of the buildings.
3. 100% standby generating capacity will be provided for the entire electrical requirement of the total scheme. This therefore includes standby generation for all common services, lite services, lifts etc. and also the entire electrical load for ventilation & air-conditioning lights and all office equipment.
4. This building will be sprinkled as per NBC norms.
5. Partitions/modifications for interior space /layout shall be as per client request/requirements of usable area of floor plate

DOOR SCHEDULE

TYPE	OPENING SIZE	CILL	LINTEL	REMARKS
B01	1900X2100	#0.0	+2100	INTERNAL TOILET DOOR (SINGLE LEAF)
B02	900X2100	#0.0	+2100	DRIVERS TOILET DOOR (SINGLE LEAF)
B03	1900X2100	#0.0	+2100	ELEC ROOM/ DWRS RM/ WATER (SINGLE LEAF)
B04	1200X2100	#0.0	+2100	FAN ROOM/ DWRS FIRE RATED (SINGLE LEAF)
B05	2200X2100	#0.0	+2100	AHU/LIFT ROOM (DOUBLE LEAF)
B06	3000X3000	#0.0	+3000	SUMMUM/ ROOME (DOUBLE LEAF)
B07	3000X3000	#0.0	+3000	DG ROOM/ TRANSFORMER ROOM/ SERVICE ROOM (DOUBLE LEAF) FIRE RATED
B08	2000X2100	#0.0	+2100	SHAFT DOOR (1 HRS FIRE RATED) (SINGLE LEAF)
B09	2000X3000	#0.0	+3000	GAS TRANSFORMER CHAMBER & SWITCH GEAR (2HRS FIRE RATED) (DOUBLE LEAF)
B010	3000X3000	#0.0	+3000	D.G. & SUBSTATION ROOM / PUMP ROOM (2HRS FIRE RATED) (DOUBLE LEAF)
#B01	4000X3000	#0.0	+3000	HVAC PLANT ROOM ... (DOUBLE LEAF)
B021	1600X2100	#300	+2100	TOILET DOOR
B021	1600X2100	#300	+2100	TOILET & U/S RAMP (2HRS FIRE RATED)
F01	1200X2100	#0.0	+2100	EMERCIES & LOBBY DOOR (2HRS FIRE RATED) (SINGLE LEAF)
T02	800X1800	+300	+2100	FHC DOOR

Architect Hafeez Contractor
Checked and Issued on the Professional Terminal Service only and not to be responsible for any Structural Design etc.
Signature of Architect
3rd Bank Street, Bombay 400 023. Tel:2801020

PROJECT:
REVISED BUILDING PLAN OF CYBERPARK COLONY AREA MEASURING 11.816 ACRES(LICENCE NO.180 OF 2007 DATED 02.05.2007 IN SECTOR 20, GURGAON MANESAR URBAN COMPLEX

OWNER: DLF CYBER CITY DEVELOPERS LTD.

CONSULTANT:-

DRG.TITLE:-
BASEMENT LVL-2
(F.F.L.-8400 MM LVL.)
(T.O.S.-8400 MM LVL.)

REVISION	JOB NO:-	DRG NO:- BP-102	NORTH:-
	SCALE- 1:250	DATE- 21/08/2017	
FILE:-	DEALT BY:-	CHECKED BY:	APPROVED BY:-
SIGNATURE & SEAL OF ARCHITECT:-		SIGNATURE & SEAL OF OWNER	