BASEMENT-03 AREA CALCULATION (BLOCK-C)

GROSS - A									
1	=	1	X	91.060	X	50.620	=	4609.457	SQM
2	=	0.5	X	4.335	X	18.185	=	39.416	SQM
3	=	1	X	4.335	X	5.415	=	23.474	SQM
4	=	0.5	X	2.650	X	5.415	=	7.175	SQM
5	=	1	X	2.785	X	27.020	=	75.251	SQM
6	=	1	X	15.305	X	17.040	=	260.797	SQM
7	=	0.5	X	15.305	X	2.890	=	22.116	SQM
8	=	0.5	X	78.540	X	19.930	=	782.651	SQM
				GROSS-1		TOTAL	=	5820.337	SQM
DOUBLE HEIGHT(CUT OUT) AREA									
GROSS - B									
s5	=	1	X	0.645	X	8.940	=	5.766	SQM
s6	=	1	X	5.180	X	9.195	=	47.630	SQM
s6a	=	0.5	X	1.045	X	0.045	=	0.024	SQM
s7	=	1	X	3.765	X	9.150	=	34.450	SQM
s8	=	0.5	X	0.645	X	2.525	=	0.814	SQM
s9	=	0.5	X	8.945	X	2.270	=	10.153	SQM
s10	=	0.5	X	3.225	X	12.700	=	20.479	SQM
s11	=	1	X	12.700	X	5.505	=	75.248	SQM
s12	=	0.5	X	12.700	X	12.700	=	80.645	SQM
						TOTAL	=	275.398	SQM
DOUBLE HEIGHT(CUT OUT) AREA BASEMENT-03									
						GROSS-B	-	GROSS-C	
						275.398		45.972	
				GROSS-2		229.236	SQM		
		SERVICES AREA							
GROSS – D									
s1	=	1	X	7.450	X	3.300	=	24.585	SQM
s2	=	1	X	3.250	X	9.500	=	30.875	SQM
s3	=	1	X	4.270	X	12.000	=	51.240	SQM
s4	=	0.5	X	3.090	X	12.000	=	18.540	SQM
				GROSS-3		TOTAL	=	125.240	SQM
						GROSS-1	-	GROSS-2	
NET AREA OF BASEMENT-03						5820.337		229.236	
						= 5591.101	SQM		
NET SERVICE AREA OF BASEMENT-03						= 125.240	SQM		
NET PARKING AREA OF BASEMENT-03						= 5591.101	-	125.240	
NO OF CAR ACHEVABLE						= 5465.861	SQM		
			=	5465.861	/	32	=	170.808	CARS
		OR SAY	=	171		CARS			

ARC AREA																							
GROSS - C																							
s13	=	1	X	3.14	x	12.700	X	12.700	x	90	\	360	-	0.5	x	12.700	-	3.720	x	17.960	=	45.972	sqm.
																				TOTAL	=	45.972	SQM

BASEMENT-04 AREA CALCULATION (BLOCK-C)

GROSS - A									
1	=	1	X	91.060	X	50.620	=	4609.457	SQM
2	=	0.5	X	4.335	X	18.185	=	39.416	SQM
3	=	1	X	4.335	X	5.415	=	23.474	SQM
4	=	0.5	X	2.650	X	5.415	=	7.175	SQM
5	=	1	X	2.785	X	27.020	=	75.251	SQM
6	=	1	X	15.305	X	17.040	=	260.797	SQM
7	=	0.5	X	15.305	X	2.890	=	22.116	SQM
8	=	0.5	X	78.540	X	19.930	=	782.651	SQM
						TOTAL	=	5820.337	SQM
TOTAL BASEMENT AREA					=	**GROSS - A**			
					=	5820.337		SQM	
SERVICE AREA									
GROSS - B									
s1	=	1	X	7.450	X	3.300	=	24.585	SQM
s2	=	1	X	3.250	X	9.500	=	30.875	SQM
s3	=	1	X	4.270	X	12.000	=	51.240	SQM
s4	=	0.5	X	3.090	X	12.000	=	18.540	SQM
s5	=	1	X	0.645	X	8.940	=	5.766	SQM
s6	=	1	X	5.180	X	9.195	=	47.630	SQM
s6a	=	0.5	X	1.045	X	0.045	=	0.024	SQM
s7	=	1	X	3.765	X	9.150	=	34.450	SQM
s8	=	0.5	X	0.645	X	2.525	=	0.814	SQM
s9	=	0.5	X	8.945	X	2.270	=	10.153	SQM
s10	=	0.5	X	3.225	X	12.700	=	20.479	SQM
s11	=	1	X	12.700	X	5.505	=	75.248	SQM
s12	=	0.5	X	12.700	X	12.700	=	80.645	SQM
						TOTAL	=	400.448	SQM
NET AREA OF BASEMNT -04					=	5820.337		SQM	
NET SERVICE AREA OF BASEMNT -04					=	400.448		SQM	
NET PARKING AREA OF BASEMNT -04					=	5820.337	-	400.448	SQM
NO OF CAR ACHIEVABLE					=	5419.889	SQM		
			=	5419.889	/	32	=	169.372	CARS
		OR SAY	=	169		CARS			

ARC AREA																							
GROSS - C																							
s13	=	1	X	3.14	x	12.700	X	12.700	x	90	\	360	-	0.5	x	12.700	-	3.720	x	17.960	=	45.972	sqm.
																				TOTAL	=	45.972	SQM

DRG NO. BS-6C

This is a "PROVISIONAL BUILDING PLAN" approved only for the purpose of inviting objections from the general public

STP(HQ) Member Secretary BPAC | ATP(HQ) Member BPAC | CTP(HQ) Chairman BPAC

Rana Partap Basal ADM(HQ) | DDA(HQ) Member BPAC

KEY PLAN

BUILDING - C

Architect
Hafeez
Contractor
29 Bank Street, Bombay 400 023. Tel:2661920

RSMS ARCHITECTS

RSMS ARCHITECTS PVT. LTD.
69,Nora Niwas Bhawani Kunj
(Behind D2), Vasant Kunj,
New Delhi-110070.
Tel.: 011-26898616,26898617
www.rsms-arch.com

Project:

PROPOSED BUILDING PLANS OF BUILDING – B AND REVISED BUILDING PLANS OF BUILDING–C, D, E, & F IN CYBER CITY UNDER TRANSIT ORIENTED DEVELOPMENT (TOD)POLICY FOR MIX LAND USED COLONY(70% IT/ITES/+30% COMMERCIAL) MEASURING 108.55922 ACRES IN SECTOR 24, 25 & 25–A, GURUGRAM MANESAR URBAN COMPLEX BEING DEVELOPED BY DLF CYBER CITY DEVELOPERS LIMITED

OWNER: DLF

DLF Cyber City Developers Ltd.
10th Floor DLF Gateway Tower,
DLF Cyber City,Gurugram,Haryana
Pin:122002

DRAWING TITLE: –

AREA CALCULATION BASEMENT-03& 04
BLOCK-C

REVISION	JOB NO: –	DRG NO. BS-6C	NORTH: –
	SCALE: – 1:100	DATE: – 01–04–2021	
FILE: –	DEALT BY: –	CHECKED BY:	APPROVED BY: –

ARCHITECT'S SEAL & SIGNATURE

OWNER'S SEAL & SIGNATURE